

CONSTRUCTION OF HUME PIPE CULVERTS ON BINA – KURWAI – SIRONJ PROJECT IN M. P. ON LABOUR RATES.

TENDER NO. TCIL/BPL/NIT/BKS/10-11/Civil/09/21

| S No. | Description | Qty. | Unit | Rate | | Amount |
|-------|--|------|------|------------|----------|--------|
| | | | | In figures | In Words | |
| 1 | Laying of RCC pipes including jointing, laying of granular material under and sides of pipes including dressing of sides and bottom of excavation (All Materials to be supplied by TCIL. Excavation shall be done by TCIL) | | | | | |
| | i) 1200 mm Dia | 250 | M | | | |
| | ii) 1000 mm Dia | 75 | M | | | |
| | iii) 600 mm Dia | 250 | M | | | |
| | iv) 300 mm Dia | 250 | M | | | |
| 2 | Laying of PCC/RCC including shuttering material, shuttering labour, vibrators, mixers including diesel/ petrol required for running of machineries. (All materials to be supplied by TCIL). All other machinery to be arranged by the contractor | 600 | Cum | | | |
| 3 | Cutting, bending and binding of steel reinforcement and placing in position (Steel reinforcement bars & binding wire to be supplied by TCIL) | 5 | MT | | | |

Signature of Contractors